



ITEMS LIST

Equipment	
1. Origin Bridge	Ref:J49125A
2. Buzzard Anamorphosis	Ref:J4952A
3. Snipe Anamorphosis	Ref:J4958A
4. Origin Swans Nest	Ref:J49150A
5. Bespoke Origin 2 Tower Multiplay Unit	Ref:UKJ49420SP1
5.1. Log Steppers	
6. Origin Combi Multiplay Unit	Ref:J4933A-V
7. Origin Springer	Ref:J980A
8. Origin Seesaw	Ref:J4920A
9. Wheelchair Roundabout*	Ref:J2409A
10. EuroTramp Trampoline*	Ref:R34-ETP-000A
11. Origin Pod Swing	Ref:J491A
12. Origin Cradle Swing	Ref:J498A
13. Origin Flat Swing	Ref:J490A
14. Rodeoboard	Ref:J3501A
15. Sand Digger	Ref:J5014A
16. Origin Bespoke Duck	Ref:UKJ49110SP-UK2022-03
17. Origin Observatory	Ref:UKJGP19-63 Z21-4909
18. Mound Sliding Tubes	Ref:UKJGP19-63 Z21-4917
19. Origin Reed Islets	Ref:UKJGP19-63 Z21-4920
20. Origin Climbing Mound Stacks x2	Ref:UKJGP19-63 Z21-4918
21. Origin Cableway	Ref:J518A
22. Swan Inclusive Springer	Ref:UKJ5015SPSWAN
23. Origin Boat	Ref:J49101A
24. Rope End Swing	Ref:J499A
25. What Local Birds Can You See Play Panel	Ref:UKA2PP-2P
26. What Local Mammals Can You See Play Panel	Ref:UKA2PP-2P
27. Inclusive Wheelchair Seesaw	Ref:J987B

*Drainage to help reduce standing water under trampoline and flush roundabout

Ancillaries	
28.13x 800mm High Stockading**	Ref:UKQ1030
29.12x 1200mm High Stockading**	Ref:UKQ1034
30.17x 300mm High Stockading**	Ref:UKQ1022
31.3x 3m Log for Landscaping (Balancing)**	Ref:UKQ1029
32.6x Sleeper (1200m x 195mm x 95mm) sanded and chamfered with a cross hatch on the length**	Ref:UKLANDSLEEPER
33.2x Glacial Boulders x3 (large rounded 275kg each)**	Ref:UKQ1017
34.2xBroxap Derby Standard Litter Bin 120 Litre (Black) inc. fixing kit	Ref: UKBX452550-s
35.4x Post & Rope**	Ref:UKLANDRAMP
36.Relocation of 5x Existing Picnic Tables	

**Delivery & Off-loading of Boulders and Other Landscaping Features x2

Surfacing
Area to be surfaced with 274m² of flecked wetpour at depths of:

221m²	@ 40mm
38m²	@ 50mm
15m²	@ 60mm

Colour breakdown:

29.5m²	@ Light green wetpour / black 50/50
59.5m²	@ Dark green wetpour / black 50/50
46m²	@ Turquoise wetpour / black 50/50
72.5m²	@ Light blue wetpour / black 50/50
66.5m²	@ Dark blue wetpour / black 50/50

108m² of green Notts Sports carpet at 0.6m CFH

113m² of EcoSmart Grassmat to be laid under items 14 & 21.

Supply & spread 142m² of Play Area Bark & 21 tonnes of Play Sand at 300mm depth.

- Groundworks**
- 802m² of excavation for Wetpour, carpet, bark & sand areas.
 - 338m² MOT type 1 stone 100mm depths for wetpour & carpet areas.
 - 456m² geotextile membrane for bark & sand areas.

Mounding for carpet requires 25m³ using 70/30 spoil from site and MOT type 1 stone (75m³) and capped with 47m² of concrete skim including forming and compacting.

Natural mounding to be created using spoil from site including forming and compacting topped with 10Kg bags grass seed

22m² topsoil & turf to reinstate where item 14 is being installed.

180m² Self binding gravel path inc all ground works and timber edging.

- Removals**
- Removal of existing MPU roundabout, spinning bowl, 2x play panels picnic table 4x swings & seesaw
 - Removal of 46m² existing tarmac and baseworks
 - Removal of 155m² of existing wetpour surfacing

- Miscellaneous**
- Additional Drainage to assist with standing water to be confirmed once on site with contractor.
 - Preliminaries including site setup, site storage, delivery, unloading of equipment, site welfare, heras fencing & signage and skips.
 - Post Installation Inspection.

- Added Value**
- Spares Box to include common spares, caps, bolts & screws worth £300
 - Half Day Training worth £250
 - 4 x quarterly inspections per year (Contract for 3 years 12 inspections in total) worth £1500
 - Site Opening Event (Falconry) worth £500
 - Spares Voucher worth £5,000 valid for 5 years (specific to this site only)
 - Added Value - Create a Bespoke Web Adventure Interactive Game worth £1200

PRODUCT KEY

	Wetpour		Play Sand
	Play Bark		Crushed Stone
	Nottsport Carpet		Existing Tarmac
	Seeded Mounding		Grassmat
	Free Fall		Free Space

- French drainage
- Additional French drainage

- 800mm High Logs(out the Ground)
- 1200mm High Logs (out the Ground)

Disclaimers

Drainage for underneath the J2409A Roundabout / R34-ETP-010A Trampoline has been included, this is to help prevent flooding but does not ensure that flooding will not occur.

Proposed Grassmat Safer surfacing is based on a fully established grass site (including a minimum of 150mm of good quality soil and turf).

Proposed Grassmat will follow the natural contours of the land.

Preliminaries have been included within your quotation, these equate to site setup, site storage, unloading of equipment, site welfare, heras fencing & signage and skips (this can also include supervision where necessary).

Topsoil & Seed watering is the responsibility of others and has not been costed for.

Pennington Flash Country Park

Wigan Borough Council

DATE: 05/07/2022

REF: 2206.34333(PenningtonFlash_WiganBC)

REV: -

DB: JPS

CB: AL

SCALE: NTS

